Description	Item	Quantity	Unit Price	Price
Materials				
5mm x 4-ft x 8-ft Plywood	<u>518477</u>	15	\$22.38	*
15/32-in x 4-ft x 8-ft OSB Sheathing	<u>70213</u>	9	\$17.25	\$155.25
2-in x 4-in x 8-ft Lumber	330568	48	\$3.25	\$156.00
1-in x 2-in x 8-ft Lumber	<u>4511</u>	5	\$1.75	\$8.75
1/2-in x 72-in Black Iron Pipe	22506	5	\$24.84	\$124.20
1/2-in Black Iron Floor Flange	<u>636100</u>	5	\$6.39	\$31.95
2-in Rigid Caster	<u>235611</u>	15	\$5.78	\$86.70
Kilz 2 Primer (3.5 Gallons)	1220140	1	\$58.57	\$58.57
Paint Roller Frame	<u>40383</u>	2	\$4.48	\$8.96
Paint Roller Cover	1034399	2	\$5.98	\$11.96
Paint Tray	<u>156438</u>	2	\$2.28	\$4.56
7/8-in Hole Saw	348125	1	\$10.98	\$10.98
			Materials Total	\$993.58
Fasteners				
1-in Leg x 1/4-in Narrow Crown Staples (1000)	288730	2	\$9.98	\$19.96
1-1/2-in Leg x 1/4-in Narrow Crown Staples (1000)	688859	2	\$13.98	\$27.96
#10 x 2-1/2-in Wood Screws (80)	580302	1	\$10.98	\$10.98
#10 x 3-1/2-in Wood Screws (60)	580304	3	\$11.98	\$35.94
1/4-in-20 x 1-1/4-in Flathead Machine Screws (4)	58051	5	\$1.38	\$6.90
1/4-in-20 x 2-1/2-in Machine Screws (25)	498	3	\$5.98	\$17.94
1/4-in Flat Washer	63306	60	\$0.15	\$9.00
1/4-in x 1-in Fender Washer	68882	20	\$0.16	\$3.20
1/4-in-20 Nylon Insert Nut	63403	80	\$0.15	\$12.00
			Fasteners Total	\$143.88
			Grand Total	\$1,137.46

Description	Item	Quantity	Unit Price	Price
Swivel Leveling Mount, 2-1/2" Long 1/4"-20 Threaded Stud	6111K148	15	\$7.22	\$108.30
Steel Tee Nut Inserts, 1/4"-20 (25)	90975A063	1	\$10.80	\$10.80
			Total	\$119.10

Description	Piece Length (ft)				Quantity (pieces)	Quantity (2x4x8)	Quantity (2x4x8) Rounded Up
			pieces per periaktos	number of periaktoi			
pedestal leg	2		3	5	15	3.75	4
		pieces per triangle	triangles per periaktos	number of periaktoi			
triangle edge	4	3	5	5	80	40	40
triangle middle piece	4		pieces per periaktos	number of periaktoi			
			1	5			
						Total Quantity	44

Width (ft)	Height (ft)	Count	Total Area (sq ft)	Coverage (sq ft per gallon)	<b>Number of Coats</b>
4	8	19	608	350	2
				Quantity (gallons)	3.47

Description	Length (in)				Quantity
		screws per triangle	triangles per periaktos	number of periaktoi	
triangle corner screws	2.5			5	75
		screws per triangle	triangles per periaktos	number of periaktoi	
triangle corner screws	3.5	3	5	5	75
		screws per leg	legs per periaktos	number of periaktoi	
leg screws	3.5	4	3	5	60
				Total Quantities	
				2.5-in Wood Screws	75
				3.5-in Wood Screws	135

Item	Length (in)	Length (in) Rounded Up
Floor Flange Assembly		
Floor Flange	0.210	
OSB Sheathing	0.469	
Fender Washer	0.048	
Nylon Insert Nut	0.308	
Total Length	1.03	1-1/4"
Caster Assembly		
Caster	0.095	
OSB Sheathing	0.469	
2-in x 4-in Lumber	1.500	
Flat Washer	0.055	
Nylon Insert Nut	0.308	
Total Length	2.43	2-1/2"

Item	Weight (lbs)
Periaktos	
Bottom Triangle	26.2
Middle Triangle	24.9
Top Triangle	12.9
OSB Supports	35.4
Plywood Panels	48.9
Total	148.3
Pedestal	63.5
Grand Total	211.8